

HLL Lifecare Ltd, KANAGALA

ANNEXURE

Name of the work-Shed for DG set, pump sets & fuel tank at Unipill plant.

SI.No	Description	Unit	Qty	Rate	Amount
1	Earth work excavation for Foundation & levelling removing the excavated earth to a distance not exceeding 50 M with a lift up to 1.50 m including refilling of excavated earth wherever required.	Cum	6		
2	Providing & laying M 7.5 (1:4:8) Granite or Basalt or trap jelly concrete using 40 mm & down size jelly for foundation laid in 15 cms thick layers & well compacted including curing etc complete..	Cum	6		
3	Providing, fabricating & fixing using MS square/ rectangular sections 5/6mm thick, 100X100X6/5,80x80x6/5,60X60X6/5, 50X50X6/5, MS plate with anchor bolts for roofing structure. making necessary holes in the masonry/ concrete & proper laying of the box finishing with concrete/plaster etc complete as directed by EIC.	Kg	3400		
4	Providing & fixing pre coated profile GI sheets & ridges of 0.45 mm thick of approved make all these sheets to be fixed to purling using self tapping screws or J-hooks, EPDM seal, metal washer, including labor, fixing new sheets etc complete. (Make-TATA/Jindal)	Sqm	130		
5	Oil painting for structure with one coat of primer with two coats of oil paint etc complete.	Sqm	100		
6	Painting and applying Stanvac make anticorrosive primer and paint, one coat of primer over which 2 coats of paint to be applied, including cleaning of sections, scraping, polishing etc complete. Make-Stanvac/equivalent	Sqm	100		
	Total amount				

Contractor sign with seal