

SCHEDULE OF QUANTITIES WITH RATES**AMRIT Pharmacy at Govt. Medical College and Hospital, Barpeta****Size : 21 Ft X 13 Ft = 273 SqFt**

Sl.N O.	ITEM	UNIT	QUANT ITY	Basic Rate (in Rs.)	AMOUNT (in Rs.)
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, 12mm Thk Ply with Laminate in the bottom and 8mm Thk Float glass in Top all complete as per architectural drawings and the directions of Engineer-in-charge	SqM	29.275		
2	Internal paint : 1 Coat primer, 2 coats water base paint distemper.	SqM	90.89		
3	Providing and fixing with 1.5sqmm and 2.5sqmm FRLS Copper wire, 20/25mm PVC conduit, Concealed M.S. Switch box, Modular Plates, Switches, fan Regulator, Sockets, Switches, For Light points, fan, AC, fridge, Camera Power, Computer Power, Sign board, with material and Labour.	Point	28.00		
4	Providing and fixing MDB with 1 No 2 Pole ELCB, 4 Nos Single pole MCB, Dressing, Termination and Commissioning.	Set	1.00		
5	Lan/ Networking wiring only with data socket, plate, box, labour all complete as per drawing.	Mtr	15.00		
6	providing and crimping socket for Lan wire connect to computer	Nos.	4.00		
7	providing and fixing ceiling fan 1200mm white in colour with clamp, labour all complete.	Nos.	4.00		

8	Supply, laying and testing of under noted sizes of Aluminium conductor XLPE insulated PVC sheathed & sleeved armoured and overall PVC sleeved 1.1 KV grade power distribution cables conforming to relevant IS code and as per specification in ground (in existing trenches) through pipe or on wall / racks cable trays including dressing and clamping the cable with MS zinc passivated clamps etc. as required.				
a	4 x 16 sq.mm	Mtr	30.000		
9	Supplying & making of end terminations with brass compression gland and Al. lugs for following sizes of PVC insulated and PVC sheathed/ XLPE Al. conductor cable of 1.1 KV grade as required.				
a	4 x 16 sq.mm	Set	2.000		
10	Supply,installation,testing and commissioning of Digital camera, 0.5 lux with 3/ 4 mm fixed lens with IR Leds for Day and night vision or equivalent complete as required in mini dome shape fixed type, including all wiring from the control module in existing PVC conduits complete as required. Make: honeywell, bosch, Hikvision, samsung	Set	3.000		
11	Supply,installation,testing and commissioning of 8 – channel colour HD Video Mgmt system with 8 cameras inputs Built in multiplexer, Digital Video recorder, Video motion Detection system, aalong with 15" monitor, TCPIP network feature for remote monitoring & 500GB HDD Make: honeywell, bosch, Hikvision, samsung or equilant.	Each	1.000		
12	Supply, installation , testing & commissioning 2.5trn MEGA split aircondition , including indoor and outdoor units , copper piping, drain piping, insulation, control and power cables between outdoor and indoor units, complete as required by Engineer-in Charge. Make: Voltas, Bluestar, Daikin. With 30 Mtr Copper Pipe and Drain	Set	1.000		

13	<p>MEDIUM SIZE MEDICAL STORAGE RACKS TYPE A:</p> <p>Open Wooden display laminated cabinets in plywood at the free floor area with proper provision of racks and shelves.</p> <p>Maximum height of the cabinet is depending upon the available height at the location. 600mm deep prelaminated storage unit with 18mm commercial ply shelves laminated bothside with front edge polish/painted and shutters fixed with hinges to be provided. The height of 600mm deep storage shall be 750mm from the ground. Rest of the height - 450mm wide 10mm thk clear float glass shelves to be fixed between laminated vertical 18 mm ply with back. shelves to be fix with proper bracket holders. as per layout drawing.</p> <p>Note: Storage unite to include: Shutters of 18mm thick prelamine, 10mm thick, back ply, hinges, individual locks, 150mm long 10mm dia "H" handle, edge polish/painted match with outer laminate colour.</p> <p>Make laminate :Greenlam - 283 Sky blue / Merino / Century.</p>	Sq. ft	340.88		
14	<p>COUNTER FOR MEDICAL: single level Counter of 900 mm from ground and Counter top at 1050 mm level. 18mm thk granite/marble to be used for counter top on 18mm thick commercial ply. Under counter storage unit (below 900 mm) to be fixed with individual locks and handles as per app. 600mm wide laminated door and openable counter top to be part of the counter as per design. The counter ends at both sides shall be in such a way that, it effectively separates the customers from the storage area. Cash drawer of suitable design is to be installed.</p> <p>Make PLYWOOD: Commercial. LAMINATE: GREENLAM, MARINO OR EQUIVALANT.</p>	Sq. ft	52.00		
15	Working Table, 3'0" X 2'0" with 18mm Ply top and two Vertical support in store room as per DRW, with colour laminated sheet finish.	Nos	1.00		
16	Revolving height adjustable chair with arm rest.	Nos.	5.00		

17	SIGN BOARD: Box Type Sign board with back Light and coloured transperant flex on front as per given design and letter.fittings will be with out stand.	Sft	21.00		
18	Supplying and fixing of carbon dioxide fire extinguisher type 2 kgs. Capacity of approved make with wall mounting bracket as required conforming to IS: 2878/1976 (Push type).	Nos	1.00		
	Total Amount for Work				
	Applicable Taxes & Statutory payments(Pl.specif				
	GRAND TOTAL (Final Bid Amount)				

3.25