

PROJECT: CONSTRUCTION OF CGHS WELLNESS CENTRE AND ADMIN.BLDG. AT SECTOR-13, R.K.PURAM, NEW DELHI.							
BOQ FOR LIFT WORKS							
SR. NO.	DESCRIPTION	UNIT	QTY	RATE (In Rs.)	RATE (In Rs.)	AMOUNT (In Rs.)	AMOUNT (In Rs.)
				<i>In Figures</i>	<i>In Words</i>	<i>In Figures</i>	<i>In Words</i>
1	Supplying, installation, testing and commissioning of 13 Passenger (884 Kg) Gearless lifts having contract speed of 1.5 MPS serving different floors in the lift shaft as per detailed specifications and as under:						
	Floor: 2B+G+3						
	Travel : 24 Meters (approx.)						
	Stops and Opening : 6 Stops & 6 Opening						
	Controller: AC Variable voltage and variable frequency						
	Automatic rescue device complete with dry maintenance free batteries as required						
	Operation: Microprocessor based single automatic push button / duplex selective collective/ with/ without attendant						
	Power: 415V 3phase 50 HZ, 4-wire system						
	Type of door: a. Car: power operated center opening horizontal sliding, stainless steel scratch proof (moon rock finish) b. landing doors: stainless steel scratch proof (moon rock finish)						
	A hand rail not less than 600mm long at 900 mm above floor level to be fixed adjacent to control panel in the lift car						
	Voice announcement system in the car to announce the position of the elevator in the hoist-way as the car passes or stops at a floor served by the elevator						
	Lift as per Above description complete as required.	Set	2.00				
	TOTAL COST FOR LIFT WORK						