

HLL LLIFECARE LTD, KANAGALA

Annexure

Name of the work-False ceiling work at Primary packing area at KFB

SI.No	Description	Unit	Qty	Rate	Amount
1	Providing & fixing pre coated profile GI sheets & plain sheets of 0.45 mm thick of approved make all these sheets to be fixed to purlins/angles using self tapping screws, EPDM seal, metal washer, lapping,including labor, fixing new sheets for false ceiling as per the required sizes,cut outs for light fixtures if required,civil work such as cutting the wall finishing with plastering, painting etc complete at the height of 4m. (Make-TATA/Jindal)	Sqm	125		
2	Providing, fabricating & fixing M.S pipe/Ms squares/MS angles of 25mm/40mm/50mm, MS plate with anchor bolts for roofing/false ceiling structure. Including cutting of pipe as per the required size painting of two coats of oil paint over a coat of zinc primer of approved brand & shade with making necessary holes in the masonry/ concrete & proper laying of the pipe finishing with concrete/plaster etc complete as directed by EIC at the height of 4m.	Kg	2300		
	Total amount				

Contractor sign with seal