

**TENDER**

***FOR***

**Construction of New Under Ground Water Tank at Peroorkada  
Factory at Thiruvananthapuram**

**PART-III  
PRICE BID**

**TENDER NO. HLL/ID/13/43-A  
MAY 2013**

**HLL LIFECARE LIMITED  
INFRASTRUCTURE DEVELOPMENT DIVISION**

## CONTENTS

---

S.NO	ITEM	PAGE NO.
1.	Commercial Conditions	2-4
2.	Special Conditions	5
3.	Bill of Quantities	6

## **1 COMMERCIAL CONDITIONS**

- 1.0.1 The tendered rate shall inter alia be deemed to include for the provision of all materials, process, operation and special requirements detailed in the particular specification irrespective of whether these are mentioned in the description of equipment schedule and Bill of quantities or not. It is an express condition of the contract that the tendered rates for various items in the Bill of Quantities shall be deemed to include for the full, entire and final condition of the contractor respective items of the works in accordance with the provision of the contract.
- 1.0.2 The tendered rate shall include for all taxes, duties, etc. as applicable and shall be quoted on the works contract basis for Construction of New Under Ground Water Tank at Peroorkada Factory at Thiruvananthapuram
- 1.0.3 The quoted price shall be inclusive of all taxes and duties whether payable by the contractor or to be deducted at source. This shall include those applicable among VAT, Sales Tax, Income Tax, Customs Duty, Excise Duty, Turnover Tax, Service Tax, Work Contract Tax, Octroi, Labour Welfare Cess Or any Other Taxes and Duties prevailing in respect of this contract. ANY BID STATING THAT TAXES ARE EXTRA WILL BE SUMMARILY REJECTED.
- 1.0.4 The tendered rate shall remain firm and free from variation due to rise in the cost of materials/equipment, labour or any other reasons whatsoever during the contract period and valid extension on the case may be.
- 1.0.5 The quantum of excise duty included in the tendered price, the rate at which they were assumed etc. shall be indicated in the tender.

### **1.1 UNIT RATES**

- 1.12 Only approved work will be measured on completion and priced as per rates quoted against the respective items.

### **1.2 BRIEF DESCRIPTION OF PRICING**

1.2.1. Unforeseen difficulties for which provision has not been made in the tender will in no way relieve the successful tenderer from the full execution of the work.

1.2.2 The price quoted shall be the final amount for this finished work.

### **1.3 INCOME TAX**

Any payment to the contractor as per contract will be made after deducting income tax as per the rules and regulations.

### **1.4 SALES TAX AND EXCISE DUTY**

The tenderer shall clearly indicate sales tax, Excise and other duties as applicable in his offer for carrying out this work.

### **1.6. SUBMISSION OF BILL**

1.6.1. The contractor shall from time to time prepare and submit interim bills of the work executed and on completion of the contract, he shall prepare and submit the final bill. The measurements sheets in support of the interim and final bills shall be prepared by the contractor on the basis of measurements taken by him jointly with the project engineer and the said measurement sheets shall be submitted by him with the relevant bill.

### **1.7. EXTRA ITEMS**

The contractor is bound to carry out any items of work necessary for the completion of the job even though such items may not have been included in the schedule of probable quantities or rates, such items being necessary or essential for completing the job. Variation order in respect of such additional items and their quantities will be issued in writing by the employer.

1.7.1 All shavings, cuttings and other rubbish as it accumulates from time to time during the progress of work and on completion including that of the sub-contractors and special tradesman and all materials condemned by the project engineer shall be cleared and removed from the site by the contractor without any extra charge.

1.7.2 All measuring steel taps, scaffolding, ladders instruments and tools that may be required for taking measurements shall be supplied by the contractor.

## **1.8. OVER TIME WORK**

If the contractor is required to work night or on holidays in order to maintain the time schedule he shall take prior approval from the Engineer-in-charge. He should also provide and maintain at his own cost sufficient lights as may be necessary to enable the work to proceed satisfactorily during the night.

1.8.1. The contractor shall give full facilities to all other contractors working on site. He shall also arrange his programme of work so as not hinder the progress of other trades. The decision of the Engineer-in-charge on any point of dispute between the various parties shall be final and binding.

1.8.2. It is specifically pointed out that the contractor shall not be entitled to any compensation whatsoever on account of delay in procurement or supply of controlled materials and the rates quoted in the contract are fixed till the completion of the contract.

1.8.3. The contractor shall co-operate with other agencies appointed by the owners for the work to proceed smoothly with the least possible delay and to the satisfaction of the owners, architects and the consultants.

1.8.4. The owners shall provide a source for power supply at one convenient point at site. The contractor shall at his own cost install a separate meter at the said source and lay additional cables from the said source also at his own cost. For the electricity consumed by the contractor he shall pay the owner the actual cost at the rate charged by the local authority for power for constructional purposes. The contractor shall also obtain the necessary permit for utilizing power for constructional purposes.

## **2. SPECIAL CONDITIONS**

### **2.1. EXECUTION WORK**

2.1.1. The whole of the work as described in the contract (including bills of materials, specification and all drawings pertaining thereto) and as advised by the Engineer-in-charge from time is to be carried out and completed in all parts to the entire satisfaction of the Employer. Any minor details of construction which are obviously and fairly intended, or which may not have been definitely referred to in this contract, but which are usual construction practice and essential to the work, shall be included in this contract.

### **2.2. CERTIFICATE OF COMPLETION**

- 2.2.1 The contractor shall intimate to the Engineer-in-charge in writing as and when the works are completed and put into beneficial use in order to enable the consultants to check certify to the owners to take over the plants.
- 2.2.2 The work shall not be considered as completed and put into beneficial use until the consultants have certified in writing that the same has been completed and put into beneficial use.
- 2.2.3 The defects liability period shall commence from date of such completion or any specific date mentioned therein.

## **BILL OF QUANTITIES**

Sl No	Description of item	Unit	Qty	Rate	Amount
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood,trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	Sqm	800		
2	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.				
	All kinds of soil	Cum	3450		
3	Filling available excavated earth (excluding rock) in trenches, plinth,sides of foundations etc. in layers not exceeding 20cm in depth,consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	1045		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:3:6 (1 Cement : 3 fine sand : 6 graded stone aggregate 40 mm nominal size)	Cum	50		

5	<p>Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. All works upto plinth level (Note :- Cement content considered in this item is @ 330 kg/cum.Excess/less cement used as per design mix is payable/recoverable separately).</p>	Cum	400		
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level: Thermo-Mechanically Treated bars	KG	56000		
7	Centering and shuttering including strutting, propping etc. and removal of form for :				
a	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	50		
b	Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	Sqm	825		
c	Suspended floors, roofs, landings, balconies and access platform	Sqm	370		
d	Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	140		



8	12 mm cement plaster finished with a floating coat of neat cement(for inside areas) of mix :				
	1:3 (1 cement: 3 fine sand)	Sqm	1000		
9	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	Sqm	800		
10	Finishing walls with Acrylic Smooth exterior paint of required shade :				
	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	Sqm	800		
11	Providing and fixing stainless steel ( Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, ( for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	KG	500		
12	Structural steel work riveted, bolted or welded , including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. (with GI Sections)	KG	500		

13	Painting on G.I. Sections with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
	New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution	Sqm	100		
14	Providing and laying Double Flanged (screwed / welded) Centrifugally (Spun) Cast Iron, Class B (IS : 1536) :				
a)	inlet pipe 100 mm dia C.I. Double Flanged Pipe	Meter	10		
b)	Outlet pipe 200 mm dia C.I. Double Flanged Pipe	Meter	20		
c)	Scour pipe 200 mm dia C.I. Double Flanged Pipe	Meter	20		
14	Supplying and fixing CI cover with frame for man holes:				
	455x610 mm size CI cover (low duty) the weight of the cover to be not less than 55 Kg	Each	5		
15	Supplying and fixing of GI pipes as air vent pipe: 80mm dia pipe	Meter	15		
	<b>Total</b>				

