

**HLL LIFECARE LTD,KANGALA.**

ANNEXURE

Sl. No	Description	Unit	Qty.	Rate	Amount
1	Removing of existing Urinals Brick masonry wall & partition wall with roof of size total appx=4mX1.2mX2.2m including shifting & disposing the debris as directed by Engineer-in-charge.	L/s	1.00		
2	Earth work excavation for foundation & removing the excavated earth to a distance not exceeding 50m with a lift upto 1.50m in ordinary soil or Hard murrum & shifting debris outside.	cum	64.00		
3	Providing and laying Granite and trap jelly concrete of 20cm using 40mm & down size jelly for foundation laid in 15 cms thick layers & well compacted for gutter & for hume pipe for which upto side half portion including curing etc. complete. CC 1:4:8	cum	2.50		
4	Providing & constructing brick masonry with approved quality of modular brick of standard size with necessary scaffolding, curing for basement & super structure in C.M 1:6	Cum	7.5		
5	Providing single coat of plastering (12mm) to internal surfaces including curing scaffolding , rounding of all corners wherever required smooth rendering in cement mortar 1:4 with 12mm thick plaster.	Sqm	115.00		
6	Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430X260X350mm with C./ M.S brackets, standard flush pipe and C.P brass unions and G.I.clamps complete painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. (Make-hindware/parryware/equivalent)	NO	6.00		
7	Providing and fitting in position black cuddapah slab 2.5cm to 4 cm of uniform thickness for partition of the urinals including cutting to line and level etc complete.	sqm	6.00		

8	Providing two coats of water proof cement painting of approved make, quality, colour & shade curing, necessary scaffolding & cleaning of paint stains wherever necessary etc., complete.	Sqm	390		
9	plumbing lines with all fittings like tees, elbows, bends etc make- Finolex/kisan/supreme/equivalent				
a	APVC-0.5" 12mm	Rmt	35		
b	APVC-0.75" 20mm	Rmt	105		
c	APVC-1" 25mm	Rmt	80		
d	Valve-0.5"	Nos	4		
e	Valve-0.75"	Nos	4		
f	Valve-1"	Nos	1		
10	Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580x440mm with integral type footrests, 100mm S or P trap, 10 litre low level, P.V.C. flushing cistern (all approved make) with fittings, C.I./M.S. brackets, 32 mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25 mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications, as directed by the Engineer-in-Charge of the work and including labour cost and conveyance of all materials and other incidental items which are necessary for the completion of the work. (Make-hindware/parryware/equivalent)	No	2.00		
11	Providing & laying to required line & slope roofing with corrugated asbestos cement sheets 6mm thick fixed with galvanized iron J or L hooks, bolts and nut 8mm dia C.I plain and bitumen washers over the existing purlins, rafters and trusses including removing old damaged sheets & fixing new, cost of material, labour etc complete as per specification. (Make: Swastik/equivalent)	Sqm	5		

12	Providing, fabricating & fixing M.S angle 5/6mm thick, ISLC 100X50X6,75X40X6,65X65X6, 50X50X6,40x40x6 MS plate with anchor bolts for roofing structure. Including painting of two coats of oil paint over a coat of red oxide of approved brand & shade with making necessary holes in the masonry/ concrete & proper laying of the angle finishing with concrete/plaster painting etc complete as directed. (Make-TATA/Vizag/Kamadhenu/equivalent)	Kg	100		
13	Providing & fixing of approved make standard tap for WC including all fittings (Make-Nelco/jaquar/equivalent.)	No	11.00		
14	Providing & fixing of cement door frame & shutter with all required fittings as directed by Engineer-in-charge. Appx (size0.8X2M)	No	2		
15	Providing and fixing Septic tank, Approx capacity 5000 ltrs ,including cost of materials,labour charge and fixtures, complete as per directed by engineer.(Capacity-3000/year).	Nos	1		
16	Providing and constructing Coursed stone Masonry in 1:6 cement mortar in foundation & plinth with bond stones (2 m apart) and rough quoin stones including curing, pointing etc. complete as directed.	Cum	2.5		
17	Providing and fixing Cement Window frame of appx size (0.45mX0.60m) including cost of materials , labour charge, etc. complete as per directed by engineer in charge.	Nos	1		
18	Providing and placing on terrace slab polyethylene water storage tank ISI:12701 marked with cover and suitable locking arrangement and making necessary holes for inlet,outlet and overflowpipes with fittings and base support for tank,including cost of all materials,labour,transport charges,HOM of equipments and testing complete as perspecifications as directed by Engineer-in-Charge (Make-Syntax/Ganga-Jal/equivalent)	Litres	2750		

19	Providing & laying of 32mm dia pipe of hasti /equivalent for the bore well including joint kit for old & new pipe as directed by Engineer-in-charge.	Mtr	40		
20	Providing & laying of 2.5sqmm cable of polycab/finolex/equivalent for the bore well line including joint kit for old & new cable as directed by Engineer-in-charge.	Mtr	45		
21	Providing & laying of nylon rope for the bore well motor including jointing to the old rope as directed by Engineer-in-charge.	Mtr	40		
22	Providing & fixing of cement pipe of 300mm dia to the bore well casing pipe from outside including top MS cap for pipe as directed by Engineer-in-charge.	Mtr	2		
				<b>TOTAL</b>	

**Contractor sign with seal**