

CONSTRUCTION OF SPECIALITY BLOCK AT GENERAL HOSPITAL, ERNAKULAM

PART - IV Air Conditioning Works

SI No	Item Description	Unit	Quantity	Rate Rs In figures & words)	Amount (in Rs.)
1	Supply, Installation, Testing and Commissioning of Air 1.5 TR 5 star (rated as per BEE)Cooled High Wall mounted Split Air Conditioner of consisting of high wall mounted type room unit (fan coil) with cordless remote control and one number outdoor condensing unit comprising of enegy efficient rotary compressor for operation on single phase, 230 V, 50Hz supply, fixing the outdoor unit on a raised platform as per manufacturers recommendation and fixing of room (fan coil) unit on wall, standard 4 m distance refrigerant copper piping with 13mm nitrile rubber insulation, providing and making interconnection between room & condenser as per site conditions, comprising of drain PVC pipe with insulation 4m, canvas connections, full electrical cabling from power plug near indoor unit and to outdoor unit, ODU MS stand, first charge refrigerant gas, suitable stabilizer, PVC drain pipe upto drain shat etc complete as required.	Nos	9.00		
	TOTAL PART IV - AC WORKS				