

**HLL LIFECARE LIMITED, KANAGALA**  
**HLL : U25193KL1966GOI002621**

**Annexure**

**Name of the work- Annual painting works at Unipill plant 2014-15.**

<b>Sl. No.</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
1	Providing and finishing external walls in One coats with Water Proof Cement paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. make, quality, & including curing, necessary scaffolding & cleaning of paint stains, scraping of old paint wherever necessary etc., complete.	Sqm	200		
2	Providing and finishing external walls in Two coats with Water Proof Cement paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. make, quality, & including curing, necessary scaffolding & cleaning of paint stains, scraping of old paint wherever necessary etc., complete.	Sqm	200		
3	Providing & applying of One coats of Nitcotex matt (navy blue/other dark shade) colour painting of approved make, quality & shade over existing painted surface including plastering of damaged corners, surfaces wherever required. Rubbing entire surface, cleaning of surface thoroughly by scrapping, polishing by sand paper, washing using water, scaffolding, curing etc., complete.	Sqm	100		
4	Providing & applying of Two coats of Nitcotex matt (navy blue/other dark shade) colour painting of approved make, quality & shade over existing painted surface including plastering of damaged corners, surfaces wherever required. Rubbing entire surface, cleaning of surface thoroughly by scrapping, polishing by sand paper, washing using water, scaffolding, curing etc., complete.	Sqm	100		
5	Providing & applying One coats of Oil Bound Washable Distemper of approved brand and shade on wall surface to give an even shade after thoroughly brooming the surface free from all grease, dirt, loose peases of scales, including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	200		
6	Providing & applying Two coats with Oil Bound Washable Distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	200		
7	Providing & applying One coat of Oil paint to existing painted surface, wall, doors, windows & ceiling (false ceiling) of approved brand & shade including preparation of surface by filling all cracks, cleaning, polishing, scraping etc complete.	Sqm	100		
8	Providing & applying Two coat of Oil paint to existing painted surface, wall, doors, windows & ceiling (false ceiling) of approved brand & shade including preparation of surface by filling all cracks, cleaning, polishing, scraping etc complete	Sqm	100		

9	Providing & finishing external walls in Two coats with "Apex ultima" paint and shade to give an even shade after thoroughly broomimg the surface to remove all dirt and loose powdered materials, free from mortar drops and other foreign matter including cost of materials, labour, preparation of surface by filling all cracks etc complete as per specifications, as directed by the Engineer-in-charge. Make - Asian	Sqm	1500		
10	Providing & finishing external walls in one coat with "Apex ultima" paint and shade to give an even shade after thoroughly broomimg the surface to remove all dirt and loose powdered materials, free from mortar drops and other foreign matter including cost of materials, labour, preparation of surface by filling all cracks etc complete as per specifications, as directed by the Engineer-in-charge. Make - Asian	Sqm	2000		
11	Providing & applying Two coats of Acralic wall care putty to the existing wall including preparing the surface after throughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specification.	Sqm	100		
12	Providing & applying painting in One coats with Plastic Emulsion Paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	1500		
13	Providing & applying painting in Two coats with Plastic Emulsion Paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	500		
14	Crack filling which are 3mm to 5mm & more wide by chipping applying mesh & filling non cracking putty/chemicals & making the surface smooth.(All cracks must be guaranteed for 1 year).	Rmt	25		
15	Providing and applying Acrylic wall care putty to a plastered surface of approved make, quality & including rubbing entire surface, cleaning, scaffolding etc complete (Excluding plaster)	Sqm	350		
16	Providing and making/repairing of epoxy flooring as per the existing shade with all required base work and finishing etc complete as per the direction of Engineer-in-charge.	Sqm	25		
<b>Total amount</b>					

Approved Brands:

Cement Paint - Surfaced / Nerolac

Matt Paint - Santex / Nitcotex

Oil Paint - Asian Paints / Berger

Note-

External height of the building is approx-10mtrs

Contractor sign with seal

