

**HLL LIFECARE LIMITED, KANAGALA
ANNEXURE**

Work : Fixing of Krub stones infront of Engg Dept, Unipill area & Guest house side.

Sl. No	Description	Unit	Qty	Rate	Amount
1	Earth work excavation for laying of krub stone removing the excavated earth & refilling after laying of krub stone.a) Ordinary soil directed by Engineer-in-charge.	Cum	70		
2	Providing & laying Granite or Basalt or trap jelly concrete using 40 mm & down size jelly for foundation laid & well compacted including curing etc complete. Cement concrete 1:4:8.	Cum	18		
3	Providing & laying of cement krub stone of fine finish of appx size in 12" X 4" X 12" including applying of two coats of oil paint over one coat of primer for exterior surface, must have fine finish as directed by Engineer-in-charge. Note - Test certificate must be submitted before laying for the supplied lot.	Rmt	600		
4	Removing of existing damaged krub stones/plates including stacking of usable stones/plates with shifting to a distance of 500m approx & disposing the broken stones outside etc complete as directed by Engineer-in-charge.	Rmt	400		
	Total amount				

Contractor sign with seal