

HLL Lifecare Ltd, KANAGALA

ANNEXURE

Name of the work-Providing shed at the north side of the napkin plant.

Sl.No	Description	Unit	Qty	Rate	Amount
1	Dismantling of existing cement concrete with steel & disposing the debris outside as directed by Engineer-in-charge.	Cum	1		
2	Dismantling of Brick wall with plastering & disposing the debris outside as directed by Engineer-in-charge.	Cum	5		
3	Providing & laying cement concrete using 20mm & down size Granite or trap laid 15 cms thick layers & well compacted, vibrating, curing finishing, form work, centering etc., complete.				
	(a) For foundation/Columns	Cum	5		
4	Providing, fabricating & fixing M.S angle 5/6mm thick, ISLC 125X70X5/6,100X50X6/5,75x40x6/5,65X65X6/5, 50X50X6/5,40X40X6/5 MS plate with anchor bolts for roofing structure. Including painting of two coats of oil paint over a coat of zinc primer of approved brand & shade with making necessary holes in the masonry/ concrete & proper laying of the angle finishing with concrete/plaster etc complete as directed by EIC.	Kg	2150		
5	Providing & fixing pre coated profile GI sheets & ridges of 0.45 mm thick of approved make all these sheets to be fixed to purlin using self tapping screws or J-hooks, EPDM seal, metal washer, including labor, fixing new sheets with cutting the wall/beam & finishing with civil work, painting touch up etc complete. (Make-TATA/Jindal)	Sqm	180		
6	Providing (12mm) plastering to internal surfaces including curing, scaffolding, rounding of all corners wherever required smooth rendering in CM 1:4 with 12 mm thick plaster.	Sqm	45		
7	Providing & fixing of half round PVC gutter with angles supports of size 150mm pipe and extend to the pipe with 4" pipe of length appx 3.0m at every 4-5m length with proper clamps and fittings etc complete as directed by Engineer-in-charge.	Rmt	60		
	Total amount				

Contractor sign with seal