## HLL LIFECARE LIMITED, KANAGALA

## Annexure

## Work :Fabrication work for GMP Partition in Unipill ware house.

SI. No	Description	Unit	Qty	Rate	Amount
1	Providing, fabricating & fixing M.S structures using MS suuare tubes of 100x100mm, 75x40mm,50x50mm, 40x40mm/ ISMC 125x65, 75x40, MS plate with anchor bolts for structure with bounding chemical. Including painting of two coats of oil paint over a coat of Zinc primer of approved brand & shade with making necessary holes in the masonry/ concrete & proper laying of the angle finishing with concrete/plaster etc complete as directed by EIC.	Kg	2700		
	Total Amount				

Contractor's seal with sign