

HLL Lifecare Ltd, KANAGALA

ANNEXURE

Name of the work-False ceiling at Mezzanine floor QC section.

Sl.No	Description	Unit	Qty	Rate	Amount
1	Providing, fabricating & fixing M.S angles/ square tubes 5/6mm thick, ISLC 125X70X5/6,100X50X6/5,75x40x6/5,65X65X6/5, 50X50X6/5,40X40X6/5 MS plate with anchor bolts for structure. Including painting of two coats of oil paint over a coat of zinc primer of approved brand & shade with making necessary holes in the masonry/ concrete & proper laying of the angle finishing with concrete/plaster etc complete as directed by EIC.	Kg	750		
2	Providing & fixing wall & roof panel of 30mm thick with Trapezoidal sheet top side 0.35mm TCT colour coated GI sheets bottom side (flat ribbed) 0.35mm TCT colour ocated GI sheet with PUFF insulated material inside of approved make all these sheets to be fixed to purlins using self tapping screws , EPDM seal, metal washer,sealant including labor, fixing new sheets etc complete. (Make-SINTEX/Euqivalent)	Sqm	120		
	TOTAL AMOUNT				

Contractor sign with seal