

**HLL LIFECARE LIMITED, KANAGALA****ANNEXURE**

Sl.No	Description of item	Unit	Qty	Rate	Amount
1	Demolishing brick work in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of EIC.	L/S	2		
2	Providing & laying granite or basalt or trap jelly cement concrete M15 (1:2:4) using 20 mm& down size jelly including mixing, laying, tamping, curing & smooth finishing for exposed faces & with necessary centering & form work etc., complete. Sills & coping, foundation & any other such works.	Cum	6.83		
3	Fabrication supplying and erecting M.S angle/pipes/MS squares/bolts 8/10mm thick, ISLC100X50X6/5, 75x40x6/5, 65X65X6/5, 50X50X6/5, I-section of approved section, M. S. tubular trusses of all spans with prefabricated steel applications using quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 6/8 nos of M. S. anchor bolts at each support with 10/12mm thick base plate and shoe plate. The work includes cutting, straightening, placing in position of M. S. pipes and welding wherever necessary and applying one coat of redoxide primer coat and two coats of oil paint of approved colour to all the members including cost of all materials, labours charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, lets., complete as per specification as directed by EIC.	Kg	4903		
4	Providing & Fabricating mild steel/HYSD reinforcement for R. C. C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary completeas per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications as directed by EIC.	Kg	1000		
5	Providing & fixing pre coated profile GI sheets/ridges of 0.45 mm thick of approved make all these sheets to be fixed (including bending if required) to purling using self tapping screws or J-hooks, EPDM seal, metal washer, including labor, fixing new sheets etc complete as directed by EIC.	Sqm	789		
6	Providing and fixing on wall surface 2.5kg/sq.cm H.D.P.E rain down water pipes 90mm outer dia approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labours, curing complete as per specifications.	Mtr	42		

7	<p>Supply &amp; Installation of FRP gutter to the condom plant including following works.</p> <p>a) Gutter to be install at approx.10mtr height.</p> <p>b) The size of the gutter vertical 350mm width 450mm approx.</p> <p>c) Thickness of gutter-3mm.</p> <p>d) Necessary MS clamps of size 50 X 6 @ 750mm c/c with necessary bolting with one coat of primer &amp; two coats of oil paint.</p> <p>e) Necessary civil work such as concreting &amp; plastering at end of the gutter.</p> <p>f) Removing &amp; refixing of existing AC sheets whereever required.</p> <p>g) Providing &amp; fixing of stop-end &amp; drop-end to the of the gutter etc.</p> <p>Guarantee for leakage should be for five years from the date of completion of work.</p>	Mtr	30		
TOTAL AMOUNT=					

Amount in words: \_\_\_\_\_

**Contractor Sign. and Seal**