

HLL MEDIPARK LTD						
Tender for Construction of Site Grading, Roads and Storm water drainage system for Medipark, Chengalpattu, Kancheepuram district, Tamil Nadu						
Site Grading and Levelling						
SI No	Description	Unit	Quantity	Rate (Rs.)		Total Amount
				In Figures	In Words	
1	Clearing Jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50m outside the periphery of the area cleared	Sqm	411,977.00			
2	Felling tress of the girth (measured at a height of 1m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material					
2.1	Beyond 30cm girth upto and including 60 cm girth	Nos	1,500.00			
2.2	Beyond 60cm girth upto and including 120 cm girth	Nos	500.00			
2.3	Beyond 120cm girth upto and including 240 cm girth	Nos	100.00			
2.4	Above 240cm girth	Nos	10.00			
3	Earth work excavating and depositing on bank with initial lead of 10 m & initial lift of 2m in Hard stiff clay, stiff black cotton, hard red earth, shales,murram, gravel, stoney earth and earth mixed with small size boulders.					

HLL MEDIPARK LTD						
Tender for Construction of Site Grading, Roads and Storm water drainage system for Medipark, Chengalpattu, Kancheepuram district, Tamil Nadu						
Site Grading and Levelling						
SI No	Description	Unit	Quantity	Rate (Rs.)		Total Amount
				In Figures	In Words	
3.1	All Kinds of Soil	Cum	24,293.00			
3.2	SDR - (Not Requiring Blasting) Earth work excavating and depositing on bank with initial lead of 10 m & initial lift of 2m in Soft disintegrated rock, laterite, soft rock or kankar, not requiring blasting.	Cum	5,606.00			
3.3	Hard rock measured in solid including blasting & stacking	Cum	7,475.00			
4.1	Construction of embankment with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2 (MoRT&H Specification)	Cum	80,964.00			
4.2	Construction of embankment with approved material obtained from borrow pits (within the site) with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2.(MoRT&H Specification)	Cum	80,964.00			

HLL MEDIPARK LTD						
Tender for Construction of Site Grading, Roads and Storm water drainage system for Medipark, Chengalpattu, Kancheepuram district, Tamil Nadu						
Site Grading and Levelling						
SI No	Description	Unit	Quantity	Rate (Rs.)		Total Amount
				In Figures	In Words	
5	Filling earth to required levels with approved materials obtained from cutting, in layers not exceeding 15cm to 20cm in compacted thickness, breaking clods, spreading, grading to required slopes/levels, watering and compacting with power roller to meet the required compaction as per detailed specification, including removal of existing ground topsoil containing organic matter, scarification and compaction of the cleared surface etc., with all lift and lead, machinery charges, material charges and labour chages including all etc., complete and as directed by the engineer incharge.	Cum	21,864.00			
6	Disposal of unsuitable Surplus Earth outside the proposed site, location identified by the contractor and approved by the engineer incharge, and contractor should take all the required necessary approvals from the various department including all leads and lifts and machinery charges and labour charges complete etc., as per the detailed specification	Cum	15,509.00			
	<b>Sub Total :</b>					