

ANNEX A: Schedule of Work					
Sub:	Supply Installation Testing of new Fire Alarm system at Commercial complex building and Integrating it with existing Conventional Main Fire alarm panel at -HLL Peroorkada Factory, Thiruvananthapuram				
Sl.No.	Description of work	Unit	Quantity	Rate in Rs.	Amount in Rs.
1	Supply, installing, testing and commissioning of Conventional - Photo Electric Type Smoke detector with dual chamber, base plate as per site conditions Make Apollo, system sensor	nos	10		
2	Supply, installing, testing and commissioning of Conventional - Manual Call Point Make Ravel	nos	1		
3	Supply, installing, testing and commissioning of Electronic Sounders with strobe (3 watt) Make Ravel	nos	1		
4	Supply laying of 2 X 1.5 Sq. m Cu conductor PVC insulated and sheathed armoured FRLS cable with ISI mark on the wall/Ceiling/existing cable tray etc as per specification i/c S/M cable end termination with brass land for 12 mm required. Make: Finolex, Havells, Polycab	Mtr.	240		
	Special Note:	New Fire alarm system shall be integrated with existing Main Fire alarm control panel - Conventional type, Ravel 9024 series (24 Zone)			
	Basic Price in Rs.				
	GST @ 18%				
	Gross Amount in Rs.				

(In words)

I agree to supply all the items as per schedule at the rates quoted by me as above and the terms and conditions of the tender document.

SIGNATURE OF THE CONTRACTOR